



1

2

3

4

5

STANDARD EQUIPMENT:

- Drawbar for upper hitch Ø 45 mm with supporting leg
- Hydraulic unfolding during reversing
- Cambridge roller Ø 500 mm
- Axle Ø 60 mm (only for casts Ø 450 mm axle Ø 50 mm)
- Swivel bearing sets
- Mechanical transport lock
- Hydraulic 2-hoses connection- for 9,0 m width 4-hoses connection
- Tires 10/75-15.3- for width 8,0 m and 9,0 m – tires 11.5/80-15.3
- 3-gang version for 4,0 m, 5,0 m, 6,2 m
- 5-gang version for 7,5 m, 8,0 m, 9,0 m

OPTIONAL EQUIPMENT:

- Cambridge cast Ø 450 mm
- Cambridge cast Ø 530 mm
- Cambridge cast Ø 600 mm
- Cam roller Ø 500 mm
- Crosskill cast Ø 510 mm
- Cutter cast Ø 520 mm

- Ø 610 mm pipe for water filling – smooth roller
- Lower drawbar pivoting hitch Ø 50 mm
- Warning plates with LED lights
- Tires 11.5/80-15.3 (for width 4,0 m – 6,2 m)

Ref. No.	Working width /m/	Number of rings /pcs/	Power demand /HP/	Weight /kg/
Cambridge Ø 450 mm				
9300	4,0	81	80-90	1770
9301	5,0	101	86-96	2060
9302	6,2	123	99-110	2340
9309	7,5	149	112-120	2670
9312	8,0	157	125-135	2770
Cambridge Ø 500 mm				
9303	4,0	75	80-90	1940
9304	5,0	95	86-96	2270
9305	6,2	117	99-110	2630
9310	7,5	143	112-120	3030
9313	8,0	151	125-135	3180
9361	9,0	167	140-160	3660
Cambridge Ø 530 mm				
9306	4,0	81	80-90	2200
9307	5,0	101	86-96	2570
9308	6,2	123	99-110	2960
9311	7,5	149	112-120	3420
9314	8,0	157	125-135	3580
9362	9,0	177	140-160	4150
Cambridge Ø 600 mm				
9363	6,2	123	99-110	3340
9364	7,5	149	112-120	3910
9365	8,0	157	125-135	4100
9366	9,0	177	140-160	4400
Crosskill Ø 510 mm				
9520	4,0	42	80-90	1790
9521	5,0	52	86-96	2050
9522	6,2	63	99-110	2340
9523	7,5	77	112-120	2680
9524	8,0	81	125-135	2800
Pinrings Ø 500 mm				
9530	4,0	25	80-90	1440
9531	5,0	31	86-96	1630
9532	6,2	39	99-110	1860
9533	7,5	47	112-120	2080
9534	8,0	49	125-135	2150